SCHEDULE - B

Name of the Work: Providing Asphalting to main & Cross roads of Lottegolhalli in Ward-18

Item No: 03

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
1	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clodsincluding loading & unloading, cost of labour Conveying the excavated earth to distance of upto 10kms including loading and unloading charges (P-126 I No. 19.10)	299.18	Cum	153.14	Rupees One Hundred Fifty Three And Paise Fourteen Only
2	Providing and laying stone dust (P II Sl.No.50)	45.38	Cum	180.00	Rupees One Hundred Eighty Only
3	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniforms layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired basically complete as per specifications. MORTH Specification No. 406 KSRRB M400-Construction of Median and Island with soil taken from Roadway cutting (P.No.167, I.No.20.18)	45.38	Cum	1059.48	Rupees One Thousand Fifty Nine And Paise Forty Eight Only
4	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH Chapter 5. (P-171 I No. 21.2)	4620.00	Sqm	2.38	Rupees Two And Paise Thirty Eight Only
5	KSRRB M500-10 Tack coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous / granular surface cleaned with mechanical broom complete as per specifications. MORTH specification No.503.(P.No.173, I.No.21.10.1)	4620.00	Sqm	11.63	Rupees Eleven And Paise Sixty Three Only

Technical Manager - I
Karnataka Rural Infrastructure Development
Project Implementation Unit
Vidhanavanagar, Bangalore-560 001.

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
6	KSRRB M500-18. Providing and laying semi dense bituminous concrete 25 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects complete as per specifications.With 80/100 grade bitumen (P.175/I.21.20.3)	115.50	Cum	9583.30	Rupees Nine Thousand Five Hundred Eighty Three And Paise Thirty Only
7	KSRRB M500-13. Providing and laying bituminous macadam 50mm thick with 100-120 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the requiredf grade, level and alignment and rolled as per Clauses 501.6 and 501.7 to achieve the desired compaction complete as per specifications. MORTH Specification No. 504 -Do- 50-75mm Compacted thickness (grading II) with 3.3% Bitimen (P.173 /I.21.13.2)	22.41	Cum	6571.13	Rupees Six Thousand Five Hundred Seventy One And Paise Thirteen Only
8	KSRRB M800-11.1. Painting lines, dashes, arrows etc., on Roads in two coats on New Work:- Painting lines, dashes, arrows etc., on roads in two coats on new work with ready mixed road marking paint conforming to IS 164 on bituminous surface, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at site and traffic control complete as per specifications i) Over 10cm in width. MORTH specification No.803. (P.194 I no.24.11)	267.00	Cum	96.98	Rupees Ninety Six And Paise Ninety Eight Only

20

Technical Manager
Karnataka Rural Infrastructure Development
Project Implementation Unit
Mahalakshmipuram, Bangalore-560 001.

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike